Drop Tile Method

Installation Guide

Installation Method

Note

- **Before installing your tiles, ensure the grid has been installed in accordance with the local building code.**

1. Wear clean white gloves throughout the installation process.
2. Once the grid has been installed to the required measurements and height, carefully cut penetrations in tiles for heat sensors, around sprinkler heads and light fittings as required.
3. Gently drop the ceiling tiles into position by angling the tile slightly, lifting it above the ceiling grid and placing it into position so that it is resting on the top of the grid.
4. If the tile doesn't fit the prepared spot, slightly cut off the excess to the defined measurement.
5. Repeat these steps until all tiles are installed.

Tools and materials required:

- Clean gloves
- Utility knife
- Straight edge
- Measuring tape
- Ladder or scaffolding

Acoufelt strives to fulfill the needs of their customers by producing the highest quality felt products. However due to the fine, fibrous and textural nature of the product, slight visual imperfections may be seen when viewing the product from less than 1 to 1.5 metres. These slight visual imperfections however are within normal industry manufacturing tolerances.

Distributed by GRAYKING INTERIOR SUPPLY

NSW 02 9666 6688

QLD 07 3267 6222

grayking.com.au

sales@grayking.com.au